



„ Experience of mire restoration in the Šumava National Park




*Ivana Bufková
and all sumava LIFE people*



„Landscape without wetlands is landscape without water“


Šumava National Park – important wetland area



Code	Habitat* (abbr.)	Area (ha)
7110*	Active raised bogs	373
7140	Transition mires and quaking bogs	959
7120	Degraded raised bogs	83
91D0*	Bog woodland	3001
(9410 part)	Waterlogged spruce forest	6739
6410	Molinia meadows	120
91E0*	Alluvial forests with Alnus	155
3260	Water courses	76



ŠUMAVA NP (70 000 ha)	Area (ha)	% NP
Mires	6 566	10
Other wetlands	14 930	21
All wetlands - total	20 536	31





Drained meadow spring for agriculture



Drained bog forest for forestry

- ☐ 70% of mires drained in the past
- ☐ about ½ other types of wetlands drained
- ☐ 2/3 springs drained
- ☐ for forestry, agriculture, peat mining





- ☐ longterm Restoration Programme
- ☐ first restored site - Kamerální slat' (1999)
- ☐ I.phase: 1999 – 2012 (budget NPS)
- ☐ II. phase: 2013 – 2017 (ERDF - EU)
- ☐ III. Phase : 2018 – 2024 (LIFE - EU)



Mires and wetlands

Mountain streams

Springs



Specific features of mountain restoration:

Headwater area

- Sloping gradients
- Strong vertical erosion

Important spring areas

- Frequent **springs** of helocrene type (wetland/mire springs)
- Prevailing small mountain streams of the first order

Oligotrophic or mesotrophic environment

- High proportion of mires (10% of the area)

High nature value – strong limits for implementation

- Valuable and vulnerable habitats
- Strict area protection – nature conservation
- Low accessibility – limits for technique

Main solved problems

- Surface drainage
- Rill erosion
- Regulated small mountain streams – of the 1st and 2nd order, incorporated into drainage system
- Piped drainage – foothill
- Manual and industrial peat extraction




Restoration technologies have to be modified

Micro-catchment approach

- ☐ springs
- ☐ small streams (1. level)
- ☐ wetlands/mires

*Water units are interlinked
– complex solution is optimal*



Primary question :

Are we dealing with stream or simple ditch?

- **Drainage ditches have to be „eliminated “**
 - blocked and infilled
- Streams can not be blocked!
- **Streams have to returned to its natural courses**




DITCHES ARE ELIMINATED = BLOCKED

STREAMS ARE RETURNED TO ORIGINAL COURSE




How to remove drainage ditches?

- **Blocking and infilling by soil**
- Both steps have to be always done!!!
- Simple infilling is not enough in sloping surface:
 - High risk of erosion near bottom
 - Increasing of water table is not sufficient
- Blocking by cascade of **woody dams**




Target Water Table Concept

- Fore selected habitats (mires, springs)
- Target water table determinates number and position of dams
- It corresponds to the natural water table




Habitat type	Target Water Table (cm under surface)
Bog	5
Spruce mire	5-10
Waterlogged spruce mire	20-35
Spring	0
Transitional mire	5-10
Moss fens	10-20



Type of woody dams


Horizontal board dam

- 2-3 layers
- Geotextilie



Vertical plank dam

Soil „packaging“ of each dam




Peat dam

- Only mined bogs on flat surface

Infilling of dammed ditches – important phase of restoration

- **Prevention of erosion**
- Enhancing **terrestrialisation**
- Enhancing **peat-forming processes**
- **Competition with time** (and decomposition)
- Upper shallow water (30-50cm) left

- **Peat** (optimal but lack of material)
- **Mineral soil, vegetation tussocks** (outside of bogs)
- **Hedges** (clustres of branches) – well used
- **Vegetation**



- **Shallow ditches** are able of quick spontaneous terrestrialisation
- **Large and deep channels** need support
- **Re-vegetation** by *Sphagnum* clusters and other mire and wetland species

Gradual disappearing of ditches from landscape





1. Simple returning into preserved **historical stream bed**



2. **Free releasing** into original course
(initiation of spontaneous stream re-establishment)



3. Creation of **new stream bed** in the historical stream course



4. Increasing of stream bed and re-waving of eroded ditch
(ditch was created in line of former stream)




Use of machines wherever possible

- Shift from manual work towards using of light machines
- **Limits:** risk of damage (peat subsidies, mechanical damage, surface erosion tracks)
- **Advantages:** more stabile and effective ditch damming and infilling, lower risk of erosion, restoration of capillar streams

Etapa II: 2013-2014

Former Iron Curtain


- 80ha
- 2013-2014
- 1,8km closed ditches
- Restored streams 0,6km
- 115 000 EUR




Drainage along former „Iron curtain“ – Černohorský močál mire II phase



- 80ha
- 2013-2014
- 1,8km of blocked ditches
- restored small stream
- 115 000 EUR



Revitalizace dolního toku Hučiny v Hornovltavském luhu




First restored stream Hučina - 2013





Before restoration



After restoration



- implementation **2005**
- 17ha
- 2,8 km ditches
- 221 woody dams
- ca 13000 EUR






TRANSBOUNDARY PROJECT – 4 PARTNERS

- ❖ Administration of Šumava NP – coordinating beneficiary
- ❖ NP Bavarian Forest
- ❖ BUND Naturschutz in Bayern e.V.
- ❖ The University of South Bohemia in České Budějovice



Jihočeská univerzita
v Českých Budějovicích
University of South Bohemia
in České Budějovice



MAIN GOALS:

- ❖ Hydrological restoration of mires and wetlands on the area 2059 hectares
- ❖ Improvement of habitats for black grouses (*Tetrao tetrix*)
- ❖ Involvement of public into mire restoration and increase of public awareness

Start: 01/08/2018 - End: 31/12/2024




EXPECTED OUTPUTS:

- > Restored **drained** mires and wetlands on the area 1672ha
- > Restored **industrially mined** peatbog Vlčí jámy on the area 17ha
- > Restored **bog forests** (spruce mires) (4ha)
- > Improved habitats for **black grouses** on the area 152ha
- > Restored **hydrological links** in landscape on the area 418ha
- > Restored disturbed **mires** in the vicinity of **settlements** (21ha) - GER

- **2059 ha in total**
- **80 km of blocked drainage ditches**
- **14 km of restored mountain streams**

47 project sites



- Reduction of CO₂ emissions by 125t/year
- Increasing of water accumulated in wetlands by 170 000 m³
- Improvement of cooling effect of wetlands in landscape


Current state of 30.8.2023

Total project sites (CZ)	43
Restored sites	32
Ongoing restoration	9
Restored area	1450 ha
Restored streams	26 km
Dammed and infilled ditches	155 km



Restored natural stream, blocked ditches and created small pools in the site Rybarný I

All sites implemented in 2019-2022



Dactylorhiza majalis sp. *turfosa* in the site Rybarný I

BLOCKING AND INFILLING OF DITCHES



RESTORATION OF SMALL STREAMS



RELEASE OF TREE CANOPY



TARGET WATER TABLE CONCEPT


REMOVAL OF PIPED DRAINAGE



TREE FELLING





MANUAL MOWING



- MULCH APPLICATION ON BARE PEAT
- SURFACE TREATMENT
- REMOVING OF DEGRADED SURFACE SOIL LAYER IN FENS

Pod Skelnou



Area (ha)	42
Blocked ditches (km)	8,1
Restored streams (km)	3,9
Implementation	2020 - 2021
Costs	238 043 EUR

- large springs
- small streams
- fens and meadow wetlands

Large, drained and totally destroyed spring



Blocking of drainage ditches, infilling of large pits from bank soil deposits

Po revitalizaci říjen 2022



Po revitalizaci prosinec 2021



Odvodněné prameniště před revitalizací (2019)




Trasa potoka rýhou před revitalizací (2018)



stav před revitalizací
A) 13. 6. 2019


stav po revitalizaci
B) 1. 6. 2022

na konci vegetační sezóny
C) 22. 8. 2022





Malý Bor






Area	67 ha
Ditch removal	5 km
Stream restoration	4,6 km
Implementation	2021 - 2022









Zrušený odvodňovací kanál







Hladina podzemní vody na lokalitě Dobrovodské louky před a po revitalizaci




- Damming of ditches – TWT concept
- Restoration of springs and small stream
- Release of dense tree canopy
- Support of peat-forming vegetation






Raising stream bed – up to 60 cm higher, re-waved stream course

Position of water table in the site Gerlova Hut' (GH) before and after restoration





Position of water table in the site Vchynice - Tetov (VT) before and after restoration




Nové údolí

Area	59 ha
Closed ditches	9 km
Restored streams	1,6 km
Implementation	2020


Beech forest



Nové údolí




CELKOVÝ SITUACNÍ VÝKRES STÁVAJÍCÍHO STAVU



BEFORE RESTORATION

CELKOVÝ SITUACNÍ VÝKRES NÁVRHOVÉHO STAVU



AFTER RESTORATION



Prameniště před revitalizací 2019



Revitalizace 2020

Prameniště před revitalizací 2019 – dolní část



Stav po revitalizaci 2022

Nové Údolí – obnova lesního potoka, převedení do zachovalého původního koryta



Nové Údolí – obnova lučního potoka, převedení do původního koryta







Stožecká



Rozloha	29 ha
Odvodňovací kanály	8,6 km
Obnova potoků	2 km
Doba realizace	2020 - 2021



Stožecká – obnova trasy potoka, vyměščení



**Stožecká – výsledek rozvlnění a vymělčení napřímeného erodujícího potoka,
pohřbené hráze ve dně**





Vlčí jámy – mined peatbog



Area	46 ha
Blocked ditches	9 km
Implementation	2021
Costs	61 122 EUR



Vlčí Jámy

Illecebrum verticillatum

- rare CI species
- specific measures



RESTORATION MEASURES:

- Blocking of ditches
- Surface treatment – pools, etc.
- Vegetation spreading
- Mulch material
- Tree felling
- Active management of *Illecebrum*

Intensive both surface and subsurface drainage



Blocking of subsurface ditches



Blocking of surface ditches



Digging of shallow surface depressions and pools

Re-establishment of peatforming processes

- Returning of *Sphagnum* mosses
- Spreading of mulch material








Area	83 ha
Ditches (km)	5
Restored streams (km)	0,3
Implementation	2021 - 2022



Water table in site Rokytecké slatě (RO) before and after restoration









Restoration 1999 - 2022	
Total restored area	1910 ha
Restored natural streams	28 km
Blocked and infilled ditches	190 km



RESTORATION



MONITORING



SHARING EXPERIENCE



COMMUNICATION



Monitoring and assessment of restoration success D1 - NPS


EVALUATION OF RESTORATION EFFECT ON:

- > **Water table**, runoff and water retention in landscape
- > **Water quality** in catchment
- > **Species diversity** and populations of rare species (black grouses)
- > **Soil processes** – peat decomposition, gas emissions
- > **Cooling effect** of restored mires and wetlands
- > **Socio-economic impacts**



„LIFE for MIREs“ – *inspirative dissemination actions*“

- > **Voluntary actions „Days for mires“**
- > **Tutorial programme** for schools and **textbook** about water and wetlands
- Popular **educative film** about wetlands
- Pictured popular **book „Water lost and returned“**
- **Manual** for restoration of mountain wetlands
- Two **professional conferences** – about monitoring and restoration methods



PROJECT TEAM



Sabina Navrátilová
PROJECT MANAGER



Ivana Bufková
EXPERT GUARANTEE



Lukáš Linhart
PR MANAGER



Martin Koudelka
FINANCE MANAGER



Eva Zelenková
ASISTENT



Claudia Schmidt
KOORDINÁTOR ZA
NP BAVARIAN FOREST



Renata Placková
FIELD WORKER



Tomáš Doležal
FIELD WORKER




Eliška Václavíková
FIELD WORKER



Jan Zelenka
FIELD WORKER



Zuzana Urbanová
KOORDINATOR ZA
JIHOČESKOU
UNIVERZITU



Melanie Kreuz
KOORDINATOR ZA
BUND NATURSCHUTZ
IN BAYERN E.V.

An aerial photograph of a forest landscape. The image shows a dense forest of evergreen trees. In the center, there is a large, irregularly shaped area of lighter green, which appears to be a wetland or a clearing. Several small, dark, irregular shapes are scattered throughout the landscape, likely representing ponds or small lakes. The overall tone of the image is green, with varying shades indicating different vegetation and water levels.

Thanks' for attention

Landscape without wetlands is landscape without water